



AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT			1. CONTRACT ID CODE		PAGE OF PAGES 1 2		
2. AMENDMENT/MODIFICATION NO. A001		3. EFFECTIVE DATE July 6, 2011		4. REQUISITION/PURCHASE REQ. NO.		5. PROJECT NO. (If applicable)	
6. ISSUED BY Contracting Officer Department of State American Embassy Islamabad		CODE GSO		7. ADMINISTERED BY (If other than Item 6) CODE			
8. NAME AND ADDRESS OF CONTRACTOR (NO., street, city, county, State, and ZIP Code) Offerors				9a. AMENDMENT OF SOLICITATION NO. S-PK330-11-Q-5572			
				X 9b. DATED (SEE ITEM 11) July 6, 2011			
				10a. MODIFICATION OF CONTRACT/ORDER NO			
				10b. DATED (SEE ITEM 13)			
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS							
<p>[x] The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers [] is extended, [X] is not extended</p> <p>Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning <u>2</u> copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers.</p> <p>FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.</p>							
12. ACCOUNTING AND APPROPRIATION DATA (If required)							
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.							
A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.							
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b)							
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:							
D. OTHER (Specify type of modification and authority)							
E. IMPORTANT: Contractor [] is not, [X] is required to sign this document and return <u>2</u> copies to the issuing office.							
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) The RFQ is amended as follows: <ol style="list-style-type: none"> Attachment # 3, solicitation pages (27 & 28) point 3.10 & 3.11 are being replaced with attached highlighted 3.10 & 3.11 statement. Attachment # 3 solicitation page 28 point 3.14 (PLUMBING) is being deleted from statement of work rest of the "SOW" remains unchanged. <p>Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.</p>							
15A. NAME AND TITLE OF SIGNER (Type or print)				16A. NAME OF CONTRACTING OFFICER Monica S Ewing			
15B. NAME OF CONTRACTOR/OFFEROR BY _____ (Signature of person authorized to sign)		15C. DATE SIGNED		16B. UNITED STATES OF AMERICA BY  (Signature of Contracting Officer)		16C. DATE SIGNED 7-6-11	

waterproofing layer under the base concrete prior to cast the concrete. Driveway shall be connected up to the street road including the side curbs. Remove old storm drains and provide new storm drains of reinforced concrete base and sides with mild steel angle iron grating. The space among the angle irons shall be less than the heel size. Grating shall be painted with three coats of paint over rest proof primer as specified above in the enamel paint section. Please note that terrace will be upgraded by tiles instead of terrazzo floor. Contractor shall provide samples for approval before start the work.

Terrace tiles:



3.10 KITCHEN UPGRADE: Remove old tiles, cabinets and plumbing and install new floor tiles, cabinets as per interwood kitchen sample code beech wood. Install new plumbing system, drains, cold and hot water piping, sink, sink mixer, counter top of granite marble, exhaust hood, duct (interwood recommended) and its installation, complete wiring, conduit replacement, paint complete in all respects. Prepare jambs of the windows and glass doors right in plumb by using cement sand mortar of ratio 1:3 one part of cement and three parts of sand including curing, scaffolding, metal lath, corner beads etc. and reinstall security grills by the same way that was installed complete in all respects. Contractor shall provide optional plans for approval to COR.



3.11 SERVANT QUARTERS: Renovate servant quarters, remove all crumbling plaster, re-plaster and paint the entire interior and exterior as per exterior finish mentioned above in item # 2.4a. Remove all plaster from outside and re-plaster with fine sand and cement, the ratio shall be 1:3 for all exterior plaster and repair work. Remove and install new solid core door with deodar wood frame as per item 2.5 including mesh screen door.